



Portable vacuum Solutions-Concrete precast site – 2018



TASK

IBS were requested to provide a solution to pick up concrete dust on a batching plant where dust was becoming an issue.

Options

1. We had to provide a unit that can be moved about and emptied easily.
2. We had to be a certain weight as limited with lifting equipment onsite.
3. We had to be an easy to operate system that could be used at night

Solution

We offered the 16.5kw standvac with big bag filling

System components

1 x 16.5kw 32 a standvac

3x 10m hose

2 x 1m³ big bag

1 x 32 a cable 10m